ALR ENGINEERING & TESTING

Civil & Geotechnical Engineering w/ Material Testing 18361 Symeron Road, Apple Valley, Ca. 92307 760-810-2031 Cell # - 760-242-3130 Office #

(ALRengineeringtesting@gmail.com)

PRELIMINARY HYDROLOGY STUDY

APN 0438-165-33

A 6.19 acre lot located on the South side of Rock Springs Rd, County of San Bernardino, State of California

Project:

Deep Creek Road Gas Station

Prepared for:

Mike Maida

c/o Steeno Design Studio 11774 Hesperia Road, Suite B Hesperia, Ca 92345

February, 2018

Project No. 1801379

ALR ENGINEERING & TESTING

Civil & Geotechnical Engineering w/ Material Testing

18361 Symeron Road, Apple Valley, Ca. 92307 760-810-2031 Cell # - 760-242-3130 Office # (ALRengineeringtesting@gmail.com)

Project No. 1801379

REGISTION STEP No. 74782

STATE OF CALIF

February 2, 2018

Mike Maida

c/o Steeno Design Studio 11774 Hesperia Road, Suite B Hesperia, Ca 92345

Attention:

Mr. Tom Steeno,

Subject:

Preliminary Hydrology Study for APN: 0438-165-33, located on the South side of Rock Springs Road, County of San Bernardino, State of California.

In accordance with your authorization, ALR Engineering & Testing has prepared a Preliminary Hydrology Study for a proposed commercial development on a 6.19 acre lot. The enclosed report contains the results of our hydrology study considerations, conclusions, and recommendations. Our efforts were directed towards providing recommendations to the County of San Bernardino for the entitlement process for the proposed development with respect to onsite storm water runoff and onsite retention.

We sincerely appreciate the opportunity of being service to you on this aspect of the project. Please do not hesitate to call us should you have any questions regarding the content of the reports

Respectfully submitted,

ALR ENGINEERING & TESTING

John/Longoria, EVT, QSP NICET III, CESSWI, ICC

Senior Associate Engineer

Stephan M. Longoria FE, QSD/P Registered Civil Engineer

Engineers Do It To Your Specifications - Engineering Excellence

Table of Contents

Table of Contents	1
Nomenclature:	2
Introduction:	3
Proposed Development:	3
Topography:	3
Phase II Small MS4 Permit:	4
Storm Water Runoff Data:	4
Off-Site Runoff:	
Post Development Runoff Volume:	5
Onsite Retention:	
Conclusion:	6
APPENDICIES	7

Google Map

Assessor's Map

Topographic Plat

Record of Survey

Preliminary Site Plan

Apple Valley South Quadrangle Map (reduced)

FEMA FIRMette

Soil Map

Soil Description

Precipitation Data

Figure C-3

Hydrograph

Nomenclature:

4	feet	L_{o}	overland flow path length
66	inch	Ü	
<	less than	MAD	Maan annual annuivitation
		MAP	Mean annual precipitation
>	greater than	max	maximum
ac	acre	MEP	maximum extent practicable
ac-ft	acre – feet	mi	mile
APN	Assessor's parcel number	min	minimum
ARC	antecedent runoff conditions	misc	miscellaneous
Ave	Avenue	MPD	Master Plan of Drainage
DMD _a	least manner comment man et leas	msl	mean sea level
BMPs	best management practices	MWC	municipal water company
С	Rational Method runoff coefficient	MWD	municipal water district
			1
Caltrans	California Department of Transportation	NPDES	National Pollutant Discharge Elimination System
CDMG	California Division of Mines & Geology	NRCS	National Resource Conservation Service
cf	cubic feet	14100	Transmit Rebouree Combervation out vice
cfs	cubic feet per second	o.d.	outside diameter
City	City of Hesperia	O&M	
		Occivi	Operations and maintenance
CL	Center Line	PM	Parcel Map
CMP	corrugated metal pipe		*
CN	SCS curve number	Ped.	Pedestrian
Cnl	open channel	0	fl(-f-)
County	County of San Bernardino	Q	flow rate (cfs)
C_p	pan coefficient	Qty	quantity
Ct	Court	R.C.E.	Registered Civil Engineer
T) A	4	RCP	reinforced concrete pipe
DA	drainage area	Rd	Road
d/s	downstream		
DMA	drainage management area	req'd	required
DWR	California Department of Water Resources	RWQCB	California Regional Water Quality Control Board
	•		
E	evaporation	S	second
EGL	energy grade line	SCS	Soil Conservation Service
		sf	square feet
FEMA	Federal Emergency Management Agency	St	Street
FIP	Finance and Implementation Plan		
FIRM	-	tc	time of concentration
	Flood Insurance Rate Map	tp	time from start of storm to peak runoff
ft	feet		rain storm duration
ft/s	feet per second	t _r	
		T	transmissivity
g	acceleration due to gravity	TR	Tract Map
gpm	U.S. gallons per minute	TR-20	SCS Technical Release Number 20
gpd	U.S. gallons per day	TR-55	SCS Technical Release Number 55
gpd/ft²	U.S. gallons per day per square foot		
Spart	o.o. ganons per day per square foot	UDMA	undeveloped drainage management area
H	total hydraulic head	UMP	Urban Management Plan
h	horizontal	u/s	-
			upstream
HEC	Hydrologic Engineering Center	USACE	U.S. Army Corps of Engineers
HEC- HMS	HEC-HMS Computer Program	USEPA	U.S. Environmental Protection Agency
HGL	hydraulic grade line	USGS	U.S. Geological Survey
hr	hour		
		V	volume
i	rainfall intensity	v	vertical
ia	initial abstraction		
i.d.	inside diameter	WS	water surface
imp		WQMP	Water Quality Management Plan
шир	impervious		
. ^	impervious	*** \$1111	, and Quality islandgement i lan
in	inch	,, Q1111	was Quarty Management Man

Introduction:

The owner of a APN: 0438-165-33 is proposing the subdivision and the construction of a convenience store gas station. This lot is located in the County of San Bernardino on the Southwest corner of Rock Springs Rd and Deep Creek Rd. The purpose of this preliminary hydrology study is to provide the County of San Bernardino with information to consider for the land use entitlement process of developing the discretionary conditions of approval. This study will reference available data researched to discuss off site storm water runoff that may impact the lot. Another topic this study will include is a discussion about the hydrology component associated with Water Quality Management Plans. Some preliminary calculations for onsite storm water runoff will be analyzed and discussed.

Proposed Development:

A reduced copy of a Site Plan provided by Steeno Design Studio of the proposed development can be found in the appendix of this report. A review of the site plan found several features proposed for development. Two buildings are proposed to be constructed on site which include the convenience store and a drive through restaurant. Other proposed structures include a fuel pump canopy, a well pump house and a trash enclosure. Additional on-site improvements will include the construction of drive aisles, parking areas, walkways, landscaped planters/fingers and concrete curb/gutters.

Per Record of Survey 03-227, the net area of the lot to be subdivided was calculated to be approximately 6.285 acres (copy included). This area was based upon the space enclosed by the bearing and distance of the lines as shown in the map. It can be noted that the area listed in the County Assessor's Map (copy included) for the APN number of 6.192 ac does not match the net area determined from the RS.

The Site Plan shows the proposed property line boundaries of the new parcel for the development. The proposed net area of the parcel to be created was found to be approximately 1.50 acres. This area is subject to change depending on the requirements of the subdivision of the existing lot and offers of dedication to the County for public use. Per the site plan, 1.36 acres of this area will be covered with impervious surfaces including the items previously discussed. It is anticipated that the area of impervious surfaces may change.

Topography:

A topographic survey was performed by a licensed land surveyor over the area for the proposed development. In the appendix of this report is a reduced copy of the topographic survey. A review of the survey found that the project site is relatively flat, with an elevation change not exceeding more than four (4) feet from the highest point to the lowest point. The longest course water would have to flow across the lot experiences approximately two (2) feet in elevation change.

The survey also found the low point of the project site to be a sump. This condition indicates that any onsite runoff may not discharge from the property. The the sump was found to be approximately 1.33 feet in depth. If the capacity of this sump were exceeded, then the topo indicates that the water would discharge the site in the Northeast corner and flow East along Rock Springs Rd or North along Deep Creek Rd.

A review of an aerial image provided by Google Maps (copy enclosed) did not find any topographic features conveying off-site storm water runoff through the parcel. The area surrounding the lot was found to be vegetated without any signs of erosion caused by concentrated flows. Some barren soil can be seen as a result of vehicles passing through the area creating dirt roads. The project site itself was also found to be relatively flat with a depression in the Northeast corner of the lot. Approximately 1/2 of the 1.5 acres is barren land, void of vegetation due to vehicles parking or traversing the barren area.

A review of the USGS Apple Valley South Quadrangle Topographic Map did not find any blue line streams, flowlines or contours indicating the presence of swales crossing the parcel. The lot was found to be located on a relatively flat plain of land between the Mojave River and the Ord Mountain range. See reduced copy of the map in the appendix. The map indicates that any concentrated flows of water would travel North or Northwest toward the Mojave River.

A field visit to the project site confirmed the sump condition. It was observed that another sump exists in the railroad underpass just North of the Deep Creek, Rock Springs Rd intersection. It was also observed that Rock Springs Rd. East of the project site climbs what historically may have been the bank of the Mojave River a very long time ago. It was also observed that Rock Springs Rd West of the project site climbs a slope as it approaches the current bank of the Mojave River before it drops down into the river. Observations from the field visit confirmed what was seen in Google Maps, that the project does not appear to be impacted by concentrated flows from offsite catchment areas.

Due to the proximity of the project site location being East of the Mojave River and below the elevation of the banks as determined from the site visit, FEMA flood hazard maps were also reviewed. The attached FIRMette from the FEMA National Flood Hazard Map 06071C6515J found the site located in a zone X flood area. Zone X flood areas are not subject to a flood hazard. Since the project site dose not appear to be impacted by flood waters from the Mojave River, no mitigation with respect to FEMA will be required at this time for this project.

Phase II Small MS4 Permit:

The Phase II Small Area MS4 General Permit adopted by the State and County requires all new developments to incorporate Low Impact Development (LID) Best Management Practices (BMP) the maximum extent practicable (MEP). New developments typically change pre-development hydrologic conditions by introducing impervious areas which do not typically infiltrate storm water runoff. One purpose of the WQMP is to mitigate the potential for contributing to or causing hydromodification. Hydromodification is a change to the existing drainage network caused by an increased runoff volume, velocity, frequency and a reduction in infiltration and flow time to reach peak flows.

Per Section E.12f of the Permit, Regulated Projects that create and/or replace one (1) acre or more of impervious surface shall implement hydromodification management features. Such features shall incorporate a design that demonstrates the post development runoff flow rate does not exceed the predevelopment runoff flow rate. A review of Figure 1 in the section found the project site to be located in the geomorphic province of the Mojave Desert, more specifically, the Mojave River Watershed. The implementation level for hydromodification management in the Mojave Desert is a 10-year, 24-hour rain event. A hydrologic analysis of the pre and post development conditions for a 10-year rain event for this project site may be required.

Storm Water Runoff Data:

To determine the flow rate and volume of storm water runoff for the proposed development, data was collected from various sources in order to develop a small area runoff hydrograph. The San Bernardino County Hydrology manual was used as a guideline for the collection of data and performing calculations. Per the addendum of the manual, precipitation data was obtained from the National Oceanic and Atmospheric Administration Precipitation Frequency Data Server (NOAA Atlas 14 Vol 6 PF server). Hydraulic Soil Group data was obtained from the USDA Natural Resources Conservation Service Web Soil Survey (WSS).

The coordinates for the project site was determined from Google Maps to be at a Latitude of 34.4142° and a Longitude of -117.2252°. These coordinates were used to locate the project site in the PF Server and

WSS to get the required data for the study. See attached Point Precipitation Frequency Estimates sheet from the NOAA web site in the appendix. According to the WSS soil map, the soil on-site was identified as 119-Cajon-Wasco Sand. The soil identified falls within hydrologic soil group A. See attached soils map and soil description. Per Figure C-3 of the hydrology manual and the soil cover complex, the two (2) curve numbers (CN) of 78 and 38 were selected for the pre-development condition based upon an antecedent moisture condition (AMC) of 2 for a 10-year storm. The CN of 78 is based upon the area of barren land and the CN of 38 for the vegetated area of annual or perennial grasses. For the developed condition, the landscaped areas were assigned a CN of 32 and 98 for the impervious areas. See attached Figure C-3 from the Hydrology manual.

Off-Site Runoff:

A sump condition was found to exist onsite. Other sumps were observed to exist offsite as well. The review of the maps and exhibits under Site Discussion did not find any indication of offsite storm water runoff of significance impacting the lot. Due to the soil type and lack of erosion caused by concentrated flows, it is assumed that little runoff occurs because the soil infiltrates most of the rainfall. Drainage swales where found between Rock Springs Rd and the railroad North and to the West of the project site. These swales appeared to be in the form of ponds as no outlets were found to exist to allow water to flow into the Mojave River or North as the Topo Quad would indicate due to the railroad tracks. Due to the observed conditions, a detailed study of the surrounding area was considered unnecessary. The scope of work to develop offsite storm drain systems to mitigate the ponding water that collects in the railroad right of way is not within the scope of work for this study nor the responsibility of the developer of this small parcel of land.

Post Development Runoff Volume:

The observed topographic features for the existing condition of this lot indicates that all onsite runoff is potentially contained onsite. For the proposed development, it is recommended that a retention system be required to mitigate 100% of the runoff created by the impervious surfaces for any rain event onsite. To determine an estimated volume of retention, one drainage area (DA) discharging into a basin for the post developed conditioned will be analyzed in this section of the report to provide some additional recomendations.

A detailed study to determine the post development flow rate(s) and volume is not feasible at this time for this preliminary study. The site layout is subject to change and a precise grading plan is not available. For post development, a rough estimation will be determined. Multiple post development DMAs within the DA cannot be analyzed as the area of coverage cannot be determined from a site plan. A precise grading plan that is developed during the design phase of this project will enable a final hydrology study to be performed to determine the boundaries of the DMAs and their associated runoff rates and volumes. Therefore, it is recommended that a Final Hydrology Study be performed and submitted for review based upon the final design of the project site.

It is assumed that the proposed development will create both connected and disconnected impervious areas in the DA. The connected impervious areas will be composed of what is assumed to be the front of the buildings (longitudinal length) facing the parking lots and drive aisles. Disconnected impervious areas will be composed of planter areas abutting some of the ends and rear side of some of the structures. Other disconnected impervious areas may be separated by landscaped fingers/planter between walkways and the parking areas or drive aisles. These pervious areas are small and may intercept some runoff from the structures or walkways before they are saturated and discharge the runoff into the parking areas and eventually to a basin.

Hydrology Studio was used to determine an estimated runoff volume. For the developed DA, an analysis of a 100-year, 24-hour storm event determine the post-development runoff rate to be $Q_{100} = 1.24$ cfs and a total volume of 17,124 cf. The Kirpich method was used to determine the time of concentration and a composite curve number (CN) was developed based upon an estimation of the pervious and impervious areas.

Onsite Retention:

An analysis of a 100-year, 24-hour storm event determine that a preliminary volume of 17,124 cf of storm water runoff may potentially be generated from the proposed development. A review of all available information indicates that historically any onsite runoff does not leave the project site due the sump condition observed. It is recommended that a basin or combination of structures be constructed onsite to capture, contain and infiltrate the storm water runoff. It is recommended that an allowance be granted in determining a final design capture volume based upon a final hydrology study that may reflect any site design changes.


Conclusion:


Research of the available information for the proposed development determined that the project site does not appear to be impacted by offsite storm water runoff. A sump condition was found to exist onsite and it was concluded that no storm water runoff currently discharges from the lot. It is recommended that a retention basin be constructed onsite to mitigate 100% of storm water runoff from any rain fall event. The estimated retention volume required for the proposed development was found to be approximately 17,124 cf from hydrologic calculations. Due to the size of the development, a WQMP will be required. The results of the findings contained in this report indicate that an analysis of a 10-year storm to meet hydromodification requirements will not be necessary. It is estimated that the parcel of land is sufficient in size to be developed as proposed per the attached site plan. It is recommended that a final hydrology study be performed based upon an approved architectural site plan and a precise grading plan to verify the retention system volume requirements. It is recommended that double ring infiltrometer testing be performed in the location of the retention system at the bottom of the basin to determine the infiltration rate of the subsurface soils. The size of the retention system may become dependent upon the infiltration rate if it is very slow. The system shall infiltrate the minimum storm water runoff volume required within a time specified by the County of San Bernardino.


APPENDICIES



Imagery @2018 Google, Map data @2018 Google 100 ft







N 07'23'59" W (R)

N 07 1227

MAR ("85.1845 W "86'91'10 V)

S Sec.

SURVEYOR'S NOTES

N 01:53'49" W 203.59

1" P 15 4218. 1 65 115/57 11, USED BIOS

7.07) RAM

BISIS OF BEARINGS: TAVEN FROM THE SOUTH LINE OF THE SE 1/4 OF SECTION 19, T4M, R3W, S.B.M., PER RS 115/57, BEING N 88'04'20" E

IRON PIPE SET & TAGGED LS 5803. UNLESS NOTED OTHERWISE INDICATES FOUND MONUMENT AS NOTED. NDICATES • • •

THE PURPOSE OF THIS SURNEY IS TO ADMINISTIT THE BOUNDARES OF DOC. NO. 2003-0811522 Q.R. & INST. NO. 85-177121 Q.R. & 800K 4320 PMEE 98 Q.R.

- PER DOC. NO. 19980404800 O.R. PER RS 115/57 INDICATES RECORD DATA NOICATES RECORD DATA
- PER INST NO. 85-177121 O.R. PER DOC. NO. 2003-0811322 O.R. PROJECATES RECORD AND MEASURED VIDICATES RECORD DATA VIDICATES RECORD DATA
 - INDICATES COUNTY SURVEYORS FIELD BOOK. INDICATES REFERENCE POINT

SURVEYOR'S STATEMENT

THIS WAP CORRECTLY REPRESENTS A SURVEY WADE. BY ME OR UNDER MY DREATION W COAPFORMWOODEN WITH THE TREQUESTOR OF JOSEPHURE SOTOWINGH SEPTEMBER 2003 SUMPRICES ACT AT THE REQUEST OF JOSEPHURE SOTOWINGH SEPTEMBER 2003.

DATE 11/25/04

ONETH E. MILLER LS 5803, EXP. 06/30/06






THIS MAP HAS BEEN EXMAND IN ACCORDANCE WITH SECTION 6768 OF THE PROFESSIONAL LAND SIRRETOR'S ACT THIS $\frac{1}{12}\frac{1}{12}\frac{1}{12}$ DAY OF $\frac{1}{12}\frac{1}{12}\frac{1}{12}\frac{1}{12}$. 2004


COUNTY SURVEYOR'S STATEMENT

THIS MAP HAS BEEN FILD UNDER DOCUMENT MANIBERGLOOF __09124733 THE LOAD DIV OF DESCRIBE SOLD ANTICODE IN BOOK __123, OF This condes of Survey, Prop. B. C. A. C. A. THE RACKET OF THE PROPERTY OF \$1.00 PM. THE ANOMER OF \$1.00 PM. COUNTY RECORDER'S CERTIFICATE

ALDITOR—CONTROLLERY/RECONDER COUNTY OF SAN BERWIEDING LARRY INVICER

or A Jeffries





National Flood Hazard Layer FIRMette

M.St.849.451



Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS

Regulatory Floodway Zone AE. AO. AH. VE. AR Without Base Flood Elevation (BFE) With BFE or Depth

0.2% Annual Chance Rood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage

areas of less than one square mile zone Area with Reduced Flood Risk due to Future Conditions 1% Annual Chance Flood Hazard Zone X Levee. See Nates, Zone X

Area with Flood Risk due to Levee Zam D

NO SCREEN Area of Minimal Flood Hazard Zone X

Area of Undetermined Flood Hazard Zene D Effective LOMRs

Channel, Culvert, or Storm Sewel Levee, Dike, or Floodwall Channen and Channel and Channe

Cross Sections with 1% Annual Chance 17.5

Base Flood Elevation Line (BFE) Water Surface Elevation Coastal Transect Limit of Study معمد واغ معمد

Jurisdiction Boundary

Coastal Transect Baseline

Hydrographic Feature Profile Baseline

Digital Data Available

No Digital Data Available

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The base map shown complies with FEMA's base map

authoritative NFHL web services provided by FEMA. This map reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or The flood hazard information is derived directly from the become superseded by new data over time. This map image is void if the one or more of the following map elements do not appear. base map imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

1,500

1,000

200

220



MAP LEGEND

Special Line Features Streams and Canals Interstate Highways Aerial Photography Very Stony Spot Major Roads Local Roads Stany Spot Spoil Area US Routes Wet Spot Other Rails Water Features Transportation Background 13 7 Soil Map Unit Polygons Area of Interest (AOI) Soil Map Unit Points Severely Eroded Spot Miscellaneous Water Soil Map Unit Lines Closed Depression Marsh or swamp Perennial Water Mine or Quarry Special Point Features Gravelly Spot Rock Outcrop Saline Spot Sandy Spot **Вотоw** Pit Area of Interest (AOI) Clay Spot Lava Flow Gravel Pit Blowout Landfill 6 Soils

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

contrasting soils that could have been shown at a more detailed misunderstanding of the detail of mapping and accuracy of soil Enlargement of maps beyond the scale of mapping can cause line placement. The maps do not show the small areas of

Please rely on the bar scale on each map sheet for map measurements. Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Maps from the Web Soil Survey are based on the Web Mercator distance and area. A projection that preserves area, such as the projection, which preserves direction and shape but distorts Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. Coordinate System: Web Mercator (EPSG:3857)

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: San Bernardino County, California, Mojave River Area

Version 9, Sep 11, 2017

Survey Area Data:

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Date(s) aerial images were photographed: Feb 1, 2015-Feb 4, The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Slide or Slip

Sinkhole

Sodic Spot

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
119 CAJON-WASCO, COOL COMPLEX, 2 TO 9 PERCENT SLOPES*		2.2	100.09
Totals for Area of Interest		2.2	100.09

San Bernardino County, California, Mojave River Area

119—CAJON-WASCO, COOL COMPLEX, 2 TO 9 PERCENT SLOPES*

Map Unit Setting

National map unit symbol: hkrr Elevation: 2,300 to 3,200 feet

Mean annual precipitation: 3 to 6 inches

Mean annual air temperature: 59 to 66 degrees F

Frost-free period: 180 to 290 days

Farmland classification: Not prime farmland

Map Unit Composition

Cajon and similar soils: 65 percent

Wasco, gravelly, and similar soils: 30 percent

Minor components: 5 percent

Estimates are based on observations, descriptions, and transects of

the mapunit.

Description of Cajon

Setting

Landform: Alluvial fans

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Tread

Down-slope shape: Linear Across-slope shape: Linear

Parent material: Alluvium derived from granite sources

Typical profile

H1 - 0 to 8 inches: sand H2 - 8 to 60 inches: sand

Properties and qualities

Slope: 2 to 9 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): High to

very high (5.95 to 19.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 1 percent Available water storage in profile: Low (about 4.2 inches)

Interpretive groups

Land capability classification (irrigated): 3e Land capability classification (nonirrigated): 7e

Hydrologic Soil Group: A

Ecological site: Sandy (R030XF012CA)

Hydric soil rating: No

Description of Wasco, Gravelly

Setting

Landform: Alluvial fans

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Tread

Down-slope shape: Linear Across-slope shape: Linear

Parent material: Alluvium derived from granite sources

Typical profile

H1 - 0 to 7 inches: sandy loam H2 - 7 to 60 inches: sandy loam

Properties and qualities

Slope: 2 to 5 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): High

(1.98 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0

to 2.0 mmhos/cm)

Available water storage in profile: Low (about 6.0 inches)

Interpretive groups

Land capability classification (irrigated): 2e Land capability classification (nonirrigated): 7e

Hydrologic Soil Group: A

Ecological site: COARSE LOAMY (R030XF003CA)

Hydric soil rating: No

Minor Components

Cajon, sloping

Percent of map unit: 2 percent

Hydric soil rating: No

Wasco

Percent of map unit: 2 percent

Hydric soil rating: No

Riverwash

Percent of map unit: 1 percent

Landform: Channels Hydric soil rating: Yes

Data Source Information

Soil Survey Area: San Bernardino County, California, Mojave River Area

Survey Area Data: Version 9, Sep 11, 2017





NOAA Atlas 14, Volume 6, Version 2 Location name: Apple Valley, California, USA* Latitude: 34.4142°, Longitude: -117.2252° Elevation: 2892.87 ft**

* source: ESRI Maps ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Helm, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Pavlovic, Ishani Roy, Cari Trypaluk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

PF tabular | PF graphical | Maps & aerials

PF tabular

PDS-	based poi	nt precipi	tation free	uency es	timates w	∕ith 90% c	onfidence	intervals	(in inche	s/hour)1	
Duration		Average recurrence Interval (years)									
Datation	1	2	5	10	25	50	100	200	500	1000	
5-min	1.02 (0.840-1.24)	1.40 (1.16-1.72)	1.94 (1.60-2.39)	2.40 (1.96-2.96)	3.05 (2.41-3.90)	3.56 (2.76-4.66)	4.12 (3.11-5.51)	4.70 (3.46-6.48)	5.53 (3.90-7.93)	6.19 (4.21-9.19)	
10-min	0.726 (0.600-0.888)	1.01 (0.834-1.23)	1.39 (1.15-1.71)	1.72 (1.40-2.12)	2.18 (1.73-2.79)	2.56 (1.98-3.34)	2.95 (2.23-3.95)	3.37 (2.48-4.64)	3.97 (2.80-5.69)	4.44 (3.02-6.59)	
15-min	0.588 (0.484-0.716)	0,812 (0.672-0.992)	1.12 (0.924-1.38)	1.38 (1.13-1.71)	1.76 (1.39-2.25)	2.06 (1.60-2.69)	2.38 (1.80-3.18)	2.72 (2.00-3.74)	3.20 (2.25-4.58)	3.58 (2.44-5.31)	
30-min	0.414 (0.342-0.506)	0.572 (0.472-0.700)	0.790 (0.650-0.970)	0.974 (0.796-1.21)	1.24 (0.980-1.58)	1.45 (1.12-1.89)	1.68 (1.27-2.24)	1 .92 (1.41-2.63)	2.25 (1.59-3.23)	2.52 (1.71-3.74)	
60-min		0.371 (0.306-0.453)	0.512 (0.422-0.628)	0.632 (0.516-0.781)	0.803 (0.635-1.03)	0.941 (0.728-1.23)	1.09 (0.821-1.45)	1.24 (0.912-1.71)	1.46 (1.03-2.09)	1.63 (1.11-2.42)	
2-hr	0.190 (0.158-0.232)	0.254 (0.210-0.310)	0.341 (0.281-0.418)	0.416 (0.340-0.514)	0.522 (0.412-0.666)	0.606 (0.470-0.792)	0.696 (0.526-0.932)	0.792 (0.581-1.09)	0.924 (0.651-1.32)	1.03 (0.701-1.53)	
3-hr	0.155 (0.129-0.190)	0.204 (0.169-0.250)	0.272 (0.224-0.334)	0.330 (0.269-0.408)	0.412 (0.325-0.526)	0.478 (0.370-0.624)	0.547 (0.413-0.732)	0.621 (0.456-0.853)	0.723 (0.509-1.04)	0.804 (0.547-1.19)	
6-hr	0.107 (0.089-0.131)	0.140 (0.115-0.171)	0.185 (0.152-0.226)	0.222 (0.182-0.275)	0.276 (0.218-0.353)	0.319 (0.246-0.416)	0.363 (0.274-0.486)	0.411 (0.302-0.565)	0.477 (0.336-0.684)	0.529	
12-hr		0.091 (0.075-0.111)	0.122 (0.100-0.149)	0.147 (0.120-0.182)	0.183 (0.144-0.233)	0.211 (0.163-0.275)	0.240 (0.181-0.321)	0.271 (0.199-0.372)	0.313 (0.220-0.448)	0.346 (0.235-0.513)	
24-hr		0.062 (0.055-0.071)	0.084 (0.074-0.097)	0.102 (0.090-0.119)	0.128 (0.108-0.154)	0.148 (0.123-0.181)	0.168 (0.136-0.212)	0.189 (0.149-0.245)	0.219 (0.165-0.295)	0.242 (0.177-0,338)	
2-day	0.026 (0.023-0.030)	0.037 (0.032-0.042)	0.050 (0.045-0.058)	0.062 (0.054-0.072)	0.078 (0.066-0.094)	0.090 (0.075-0.111)	0.103 (0.083-0.129)	0.116 (0.091-0.150)	0.134 (0.102-0.181)	0.149 (0.109-0.208)	
3-day	0.019 (0.017-0.022)	0.027 (0.024-0.031)	0.037 (0.033-0.043)	0.046 (0.040-0.053)	0.057 (0.049-0.069)	0.067 (0.055-0.082)	0.076 (0.062-0.096)	0.086 (0.068-0.112)	0.100 (0.076-0.135)	0.111	
4-day		0.021 (0.019-0.025)	0.030 (0.026-0.034)	0.037 (0.032-0.043)	0.046 (0.039-0,056)	0.054 (0.045-0.066)	0.062	0.070	0.081 (0.062-0.110)	0.090	
7-day	0.009 (0.008-0.011)			0.023 (0.020-0.027)	0.029 (0.025-0.035)	0.034 (0.028-0.042)	0.039 (0.032-0.049)	0.044	0.052	0.057	
10-day			0.014 (0.012-0.016)	0.017 (0.015-0.020)	0.022 (0.018-0.026)	0.025 (0.021-0.031)	0.029 (0.024-0.037)	0.033 (0.026-0.043)	0.039	0.043 (0.032-0.061)	
20-day	0.004 (0.004-0.005)	0.006 (0.005-0.007)	0.008 (0.007-0.009)	0.010 (0.009-0.012)	0.013 (0.011-0.016)	0.015 (0.013-0.019)	0.018 (0.014-0.022)	0.020	0.024	0.027 (0.020-0.037)	
30-day	0.003 (0.003-0.003)		0.006	0.008	0.010 (0.009-0.012)	0.012	0.014	0.046	0.019	0.021 (0.015-0.029)	
45-day		0.003 (0.003-0.004)	0.005 (0.004-0.006)	0.006	0.008	0.010 (0.008-0.012)	0.011	0.013	0.015	0.017 (0.012-0.024)	
60-day	0.002 (0.002-0.002)	0.003 (0.002-0.003)	0.004 (0.004-0.005)	0.005 (0.004-0.006)	0.007	0.000	0.000		0.013 (0.010-0.017)		

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).

Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.



NOAA Atlas 14, Volume 6, Version 2 Location name: Apple Valley, California, USA* Latitude: 34.4142°, Longitude: -117.2252° Elevation: 2892.87 ft**

* source: ESRI Maps ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Heim, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Paviovic, Ishani Roy, Carl Trypaluk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

PF tabular | PF graphical | Maps & aerials

PF tabular


Duration T	PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches) ¹									PD	
1											
10-min	1000	500	200	100	50	25	10	5	2	11	
15-min	0.516 (0.351-0.766)				0.297 (0.230-0.388)	0.254 (0.201-0.325)	0.200 (0.163-0.247)				5-min
13-min	0.740 (0.504-1.10)	0.661 (0.466-0.948)				0.364 (0.288-0.465)	0.286 (0.234-0.354)	0.232 (0.191-0.285)			10-min
30-min (0.171-0.253) (0.236-0.350) (0.325-0.485) (0.398-0.603) (0.490-0.792) (0.562-0.947) (0.593-1.12) (0.703-1.32) (0.793-1.61) (0.793-1.61) (0.793-1.61) (0.222-0.328) (0.306-0.453) (0.422-0.628) (0.516-0.781) (0.635-1.03) (0.635-1.03) (0.728-1.23) (0.821-1.45) (0.912-1.71) (1.462-1.9) (0.315-0.465) (0.419-0.621) (0.562-0.837) (0.639-1.03) (0.824-1.33) (0.824-1.33) (0.824-1.33) (0.593-1.58) (1.05-1.86) (1.16-2.18) (1.30-2.65) (1.30-2.65) (0.386-0.570) (0.507-0.751) (0.679-1.03) (0.809-1.22) (0.977-1.58) (1.11-1.87) (1.24-2.20) (1.37-2.56) (1.37-2.56) (1.30-2.65)	0.895 (0.609-1,33)	0.799 (0.563-1.15)									15-min
Color Colo	1.26 (0.857-1.87)										30-min
2-hr	1.63					0.000	0.632 (0.516-0.781)	0.512 (0.422-0.628)	0.371 (0.306-0.453)		60-min
3-Hr (0.386-0.570) (0.507-0.751) (0.673-1.00) (0.809-1.22) (0.977-1.58) (1.11-1.87) (1.24-2.20) (1.37-2.56) 2.17 (1.53-3.11) 6-hr 0.641 0.837 1.11 1.33 1.65 1.91 2.18 2.46 (1.81-3.38) 2.01-4.10) 12-hr 0.825 1.10 1.46 1.77 2.20 2.54 2.89 3.26 3.77 (2.66-5.40) 2-hr 1.09 1.49 2.02 2.46 3.07 3.54 4.03 4.55 3.97-7.09) 2-day 1.27 1.76 2.42 2.97 3.73 4.32 4.93 5.57 6.45 1.3-day 1.37 1.92 2.67 3.28 4.13 4.80 5.49 6.21 7.22 6.45 4-day 1.45 2.04 2.86 3.52 3.52 4.45 3.92 4.45 5.93 6.72 7.81 1-day 1.45 2.04 2.86 3.52 3.	2.06 (1.40-3.06)										2-hr
12-hr 0.825 1.10 1.46 1.77 2.20 (1.45-2.19) (1.64-2.91) (1.81-3.38) 2.86 (2.01-4.10) 24-hr 1.09 1.49 (1.69-1.28) (1.21-1.80) (1.45-2.86) (2.01-4.10) 24-hr 1.09 1.49 (1.21-1.80) (1.78-2.33) (2.15-2.86) (2.01-4.10) 2-day 1.27 1.76 (1.56-2.03) (1.56-2.03) (2.14-2.80) (2.16-3.80) (3.16-4.49) (3.59-5.31) 3-day 1.37 (1.21-1.57) (1.70-2.21) (2.35-3.08) (2.88-3.82) (3.50-4.98) (3.98-5.90) (4.45-6.91) (4.90-8.05) (5.91-10.5) 4-day 1.45 (1.81-2.36) (2.52-3.30) (3.38-4.49) (3.58-4.90) (3.31-6.26) (4.80-7.47) (4.56-9.66) (6.57-11.7) 4-day 1.66 2.25 (1.97-2.56) (2.75-3.60) (3.38-4.49) (4.15-5.90) (4.77-7.02) (5.58-9.66) (6.57-11.7)	2.41 (1.64-3.58)									(0.386-0.570)	3-hr
24-hr (0.682-1.01) (0.905-1.34) (1.21-1.80) (1.45-2.19) (1.74-2.81) (1.97-3.31) (2.18-3.87) (2.39-4.48) 3.66-5.40) 24-hr 1.09 (0.965-1.25) 1.49 (1.32-1.71) 2.02 (1.78-2.33) 2.46 (2.15-2.86) 3.07 (2.60-3.69) 3.54 (2.94-4.35) 4.03 (3.27-5.08) 4.55 (3.58-5.89) 5.25 (3.97-7.09) 2-day 1.27 (1.12-1.48) 1.76 (1.56-2.03) 2.42 (2.14-2.80) 2.97 (2.60-3.46) 3.73 (3.16-4.49) 4.32 (3.59-5.31) 4.93 (4.00-6.21) 5.57 (4.39-7.21) 6.45 (4.88-8.70) 3-day 1.37 (1.21-1.57) 1.92 (2.67 (2.35-3.08) 3.28 (2.88-3.82) 4.13 (3.50-4.98) 4.80 (3.98-5.90) 5.49 (4.45-6.91) 6.21 (4.90-8.05) (5.46-9.74) 4-day 1.45 (1.29-1.67) 2.04 (2.86 (2.52-3.30) 3.52 (3.09-4.11) 4.45 (3.77-5.38) 5.17 (4.29-6.36) 5.93 (4.80-7.47) 6.72 (5.29-8.70) 7.81 (5.91-10.5) 7-day 1.56 (1.97-2.56) (2.75-3.60) 3.86 (3.38-4.49) 4.90 (4.15-5.90) 6.71 (4.74-7.02) 6.56 (5.87-9.65) 6.57-11.7)	3.17 (2.16-4.70)										6-hr
24-fit (0.965-1.25) (1.32-1.71) (1.78-2.33) (2.15-2.86) (2.60-3.69) (2.94-4.35) (3.275-0.8) (3.58-5.89) 5.25 (3.97-7.09) 2-day 1.27 (1.12-1.46) 1.76 (1.56-2.03) 2.42 (2.14-2.80) 2.97 (2.60-3.46) 3.73 (3.16-4.49) 4.32 (3.59-5.31) 4.93 (4.00-6.21) 5.57 (4.39-7.21) 6.45 (4.88-8.70) 3-day 1.37 (1.21-1.57) 1.92 (1.70-2.21) 2.67 (2.35-3.08) 3.28 (2.88-3.82) 4.13 (3.50-4.98) 4.80 (3.98-5.90) 5.49 (4.45-6.91) 6.21 (4.90-8.05) 7.22 (5.46-9.74) 4-day 1.45 (1.29-1.67) 2.04 (1.81-2.36) 2.86 (2.52-3.30) 3.52 (3.09-4.11) 4.45 (3.77-5.38) 5.17 (4.29-6.36) 5.93 (4.80-7.47) 6.72 (5.29-8.70) 7.81 (5.91-10.5) 7-day 1.57 (1.40-1.81) 2.22 (1.97-2.56) 3.11 (2.75-3.60) 3.86 (3.38-4.49) 4.90 (4.15-5.90) 5.71 (4.29-6.36) 6.56 (5.31-8.26) 7.45 (5.87-9.65) 8.68 (6.57-11.7)	4.17 (2.84-6.18)										12-hr
2-day (1.12-1.46) (1.56-2.03) (2.14-2.80) (2.60-3.46) (3.16-4.49) (3.59-5.31) (4.00-6.21) (4.39-7.21) (4.88-8.70) 3-day (1.37	5.80 (4.24-8.11)										24-hr
3-day (1.21-1.57) (1.70-2.21) (2.35-3.08) (2.88-3.82) (3.50-4.98) (3.98-5.90) (4.45-6.91) (4.90-8.05) 6.21 7.22 (5.46-9.74) 4-day 1.45 (1.29-1.67) 2.04 (1.81-2.36) 2.86 (2.52-3.30) 3.52 (3.09-4.11) 4.45 (3.77-5.38) 5.17 (4.29-6.36) 5.93 (4.80-7.47) 6.72 (5.29-8.70) 7.81 (5.91-10.5) 7-day 1.57 (1.40-1.81) 2.22 (1.40-2.56) 3.86 (2.75-3.60) 4.90 (3.38-4.49) 5.71 (4.15-5.90) 6.56 (5.31-8.26) 7.45 (5.87-9.65) 8.68 (6.57-11.7)	7.14 (5.22-9.97)									(1.12-1.46)	2-day
4-day (1.29-1.67) (1.81-2.36) (2.52-3.30) (3.09-4.11) (3.77-5.38) (4.29-6.36) (4.80-7.47) 6.72 7.81 7-day 1.57 (1.40-1.81) 2.22 (1.40-1.81) 3.11 (2.75-3.60) 3.86 (3.38-4.49) 4.90 (4.15-5.90) 5.71 (4.74-7.02) 6.56 (5.31-8.26) 7.45 (5.87-9.65) 8.68 (6.57-11.7)	8.01 (5.85-11,2)										3-day
7-day (1.40-1.81) (1.97-2.56) (2.75-3.60) (3.38-4.49) (4.15-5.90) (4.74-7.02) (5.31-8.26) (5.87-9.65) (6.57-11.7)	8.68 (6.34-12.1)								{		4-day
10 day 1.66 2.35 3.30 4.10 5.23 2.42 7.04 3.00	9.65 (7.06-13.5)					, ,,,,,					7-day
(1.47-1.91) (2.08-2.70) (2.91-3.81) (3.59-4.77) (4.43-6.29) (5.08-7.52) (5.70-8.87) (6.31-10.4) (7.09-12.6)	10.4 (7.63-14.6)	9.37 (7.09-12.6)	8.01 (6.31-10.4)	7.04 (5.70-8.87)	6.12 (5.08-7.52)	5.23 (4.43-6.29)	4.10 (3.59-4.77)	3.30 (2.91-3,81)	2.35 (2.08-2.70)	(1.47-1.91)	10-day
20-day 1.90 2.72 3.87 4.85 6.26 7.38 8.56 9.80 11.5 (5.30-7.53) (6.13-9.08) (6.93-10.8) (7.72-12.7) (8.71-15.5)	12.9 (9.41-18.0)	11.5									20-day
30-day 2.15 3.09 4.43 5.58 7.26 8.60 10.00 11.5 13.5 (3.91-2.48) (2.74-3.56) (3.91-5.12) (4.89-6.51) (6.15-8.74) (7.14-10.6) (8.10-12.6) (9.05-14.9) (10.2-18.3)	15.2 (11.1-21.2)	13.5	11.5		1 4.44						30-day
45-day 2.54 3.64 5.23 6.61 8.64 10.3 12.0 13.9 16.4 (2.25-2.92) (3.22-4.19) (4.62-6.04) (5.79-7.71) (7.33-10.4) (8.55-12.7) (9.74-15.1) (10.9-17.9) (12.4-22.1)	18.4 (13.4-25.7)	16.4	13.9								45-day
60-day 2.80 3.99 5.74 7.27 9.52 11.4 13.3 15.4 18.3 (9.44-14.0) (10.8-16.8) (12.1-19.9) (13.8-24.7)	20.5 (15.0-28,7)	18.3	15.4	13.3							60-day

Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).

Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

PF graphical

PDS-based depth-duration-frequency (DDF) curves Latitude: 34 4142°. Longitude: -117.2252°




NOAA Atlas 14, Volume 6, Version 2

Created (GMTI Sat Feb 3 00 15 24 2018


Back to Top


Maps & aerials





Large scale map





Back to Top

US Department of Commerce
National Oceanic and Atmospheric Administration
National Weather Service
National Water Center
1325 East West Highway
Silver Spring, MD 20910
Questions? HDSC Questions@noaa.gov

Court Time (2)	Quality of		Soil Group		
Cover Type (3)	Cover (2)	A	В	C	
NATURAL COVERS -	1				
Barren		78	86	91	
(Rockland, eroded and graded land)					
Chaparral, Broadleaf	Poor	53	70	80	
(Manzonita, ceanothus and scrub oak)	Fair Good	40	63 57	75	
Chaparral, Narrowleaf	_				
(Chamise and redshank)	Poor Fair	71 55	82 72	88	
		''	/*	**	
Grass, Annual or Perennial	Poor Fair	67 50	78 69	86 79	
	Good	38	61	74	
Meadows or Cienegas	Poor	63	77	85	
(Areas with seasonally high water table.	Fair	51	70	80	
principal vegetation is sod forming grass)	Good	30	58	71	
Open Brush	Poor	62	76	84	
(Soft wood shrubs - buckwheat, sage, etc.)	Fair	46	66	77	
	Good	41	63	75	
Woodland	Poor	45	66	77	
(Coniferous or broadleaf trees predominate. Canopy density is at least 50 percent.)	Fair Good	36 25	60 55	73	
carry as as assess ye percentary	Good	25	22	70	
Woodland, Grass	Poor	57	73	82	
(Coniferous or broadleaf trees with canopy	Fair	44	65	77	
density from 20 to 50 percent)	Good	33	58	72	
URBAN COVERS -					
Residential or Commercial Landscaping	Good	32	56	69	
(Lawn, shrubs, etc.)				"	
Turf	Poor	58	74	83	
(Irrigated and mowed grass)	Fair	44	65	77	
	Good	33	58	72	
AGRICULTURAL COVERS -					
Fallow		77	86	91	

SAN BERNARDINO COUNTY
HYDROLOGY MANUAL

CURVE NUMBERS
FOR
PERVIOUS AREAS

Hydrology Studio v 2.0.0.52 03-09-2018

Post Development

Hyd. No. 3

Hydrograph Type	= NRCS Runoff	Peak Flow	= 1.239 cfs
Storm Frequency	= 100-yr	Time to Peak	= 7.90 hrs
Time Interval	= 3 min	Runoff Volume	= 17,124 cuft
Drainage Area	= 1.5 ac	Curve Number	= 92*
Tc Method	= Kirpich	Time of Conc. (Tc)	≐ 5.99 min
Basin Slope	= 0.5 %	Hydraulic Length	= 395 ft
Total Rainfall	= 4.0300 in	Design Storm	= Type IA
Storm Duration	= 24 hrs	Shape Factor	= 645

Composite CN Worksheet

AREA (ac) CN DESCRIPTION 1.36 98 Impervious 32 0.14

Pervious Weighted Average

